

4. Each tender must be accompanied by a deposit of Rs. 50 in cash or Government promissory notes, as earnest money, and be superscribed "Tender for the collection of materials for road repairs and drains during 1895-96," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the President of the Municipality, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any tender, or to accept in any tender the tender for all the materials together or none which one has tendered for.

6. Within eight days of the acceptance of any tenders the successful competitor or competitors will be required to execute a contract bond (in the form which may be seen in the office) and to deposit the sum of Rs. 200 with the Municipality as a security for the due performance of the contract.

7. The names of the successful competitors whose tenders have been accepted will be posted on the notice Board in the Municipal Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On the acceptance of any of the tenders the earnest money on rejected tenders will be returned.

Statement of materials required.

Items.	Approximate quantity required.	Remarks.
Collecting and stacking quartz metal broken to size as per specification. C. Yds.	4,000	The rates to include cost of carting to the road side anywhere within Municipal limits and stacking in heaps of dimensions as per specifications not less than $\frac{1}{4}$ th of the schedule quantities will be required to be collected in each month.
Ditto do black granite of Purnaiya's Nala excavations .. C. Yds.	3,000	
Ditto do gravel .. ditto	7,000	
Burnt slab stones 3" thick including filling as in drains, &c. .. S. Ft.	10,000	The rates to include dressing and fixing at the places ordered.
Ditto do 6" thick for covering over drains and tunnels .. S. Ft.	2,000	
New rough stone work .. C. Yds.	300	The rate to include construction wherever ordered.

H. NANJUNDARAJ URS, *Vice-President.*

ALALKATTE CHANNEL DIVISION.

Notice dated the 27th June 1895.

Notice is hereby given that sealed tender will be received at the office of the Executive Engineer, Alalkatte Channel Division, Saligram, up to Saturday the 20th July 1895, for extending the Saligram Rai Channel in the Yedatore Taluk, Mysore District.

2. The proposed extension is about 12 miles long besides 12 miles of branch Channels. It must be completed in all respects including branch channels, before the close of May 1897.

3. The work will be divided into six sections and intending contractors may tender for one or more sections. An approximate estimate of the quantities of different kinds of work in each section is given below.

4. The specification of work and conditions of contract may be seen in the office of the Chief Engineer at Bangalore or of the Executive Engineer at Saligram. The sections of the channel and designs for masonry works may be seen at the Executive Engineer's office at Saligram, between the hours of 12 noon and 5 P. M., every day.

5. Tenders should be accompanied by a schedule of rates for the different classes of works, and must be superscribed "Tenders for extending Saligram Rai Channel."

6. Each tender should be accompanied by a deposit of Rs. 1,000 in cash or Government Currency Notes, in default of which such tender will be rejected.

7. The final acceptance of any tender will rest absolutely with the Chief Engineer, and no enquiries regarding the rejection of any tender will be answered.

8. The names of successful tenderers will be posted on the notice board in the Executive Engineer's Office, and intimation will be given to them. Their postal address should be enclosed with their tenders.

9. Within ten days of the acceptance of any tender, the tenderer should execute the usual contract bond and hand it over to the Executive Engineer, in default of which his tender is liable to be cancelled and his deposit money forfeited to Government.

10. The deposit money of unsuccessful tenderers will be returned to them on application after the 5th of August 1895.

Items of work.	Per.	Main Channel.			Branch Channel.		
		No. 1 Section 0 to 3 M. 47-74 chs.	No. 2 Section 3 M. 47-74 to 6 M. 50-88 chs.	No. 3 Section 6 M. 50-88 to 12 M. 9-40 chs.	No. 4 Section Bichanalli 0 to 4 miles.	No. 5 Section Gundanhalli (South) 0 to 3 M. 182-00 chs.	No. 6 Section Gun- danhalli (North) 0 to 3¼ miles.
Cutting Channel—							
Earth	C. Yds.	31,489	13,317	19,836	5,361	9,603	10,489
Gravel	"	18,895	13,185	31,351	7,575	13,569	14,817
Soft rock	"	50,847	32,231	12,939	1,166	2,089	2,664
Hard rock	"	7,394	17,683	3,545	458	764	1,090
Channel Stones—							
Mile stones	Each.	3	3	5	4	3	3
Grade stones	"	186	144	98	64	56	60
Index stones	"	184	140	95	60	53	57
Bank stones	"	..	..	48	..	..	..
Bed stones	"	..	..	50	..	..	..
Road bridges & cart panaboos—							
Excavation	C. Yds.	488	164	200	..	73	172
Concrete	C. Ft.	3,541	1,229	1,150	..	362	916
Slabs	"	..	..	..	..	367	930
Raw and burnt stone slabs for pillars, &c..	"	3,587	1,245	1,152	..	..	..
Gravelling for road way	"	1,126	390	334	..	107	306
Plastering	Sq.	27-28	9-47	11-31	..	3-67	7-34
Burnt stone in surki mortar	C. Ft.	15,158	5,623	7,932	..	3,422	7,824
Burnt brick in surki mortar..	..	1,568	553	665	..	217	434
Waste weirs and silt dams—							
Excavation	C. Yds.	1,025	526	967	..	135	270
Brick in surki mortar	C. Ft.	6,316	3,306	6,264	..	917	1,834
Rough stone pitching dry	C. Yds.	803	463	910	..	130	260
Slab stone 6" thick	C. Ft.	345	171	298	..	38	76
Concrete	..	345	171	298	..	38	76
Irrigation sluices—							
(As per standard design)	No.	15	12	22	16	..	..
Channel embankment—							
Wherever required	C. Yds.	..	..	..	18,014	4,213	36,118
Head sluice vent (3 × 4½)—							
Clearing site	L. S.	..	..	..	..	Rs.	Rs.
Excavation	C. Yds.	..	..	..	..	58	87
Burnt stone in surki mortar..	C. Ft.	..	..	..	..	1,712	2,568
Burnt brick do	"	..	..	..	..	2,624	3,936
Archwork	"	..	..	..	..	104	156
Cornice	R. Ft.	..	..	..	..	126	189
Concrete	C. Ft.	..	..	..	..	6	9
Plastering	Sq.	..	..	..	..	13-92	20-88
Teak wood work	C. Ft.	..	..	..	..	22	33
Gear rod, &c.	L. S.	..	..	..	..	Rs.	Rs.
Slab 3" thick..	C. Ft.	..	..	..	..	164	246
Do 6" do	"	..	..	..	..	72	108
Do 12" do	"	..	..	..	..	74	111
Cut stone in surki mortar	"	..	..	..	..	122	183
Pointing	Sq.	..	..	..	..	2-36	3-54